

SCHEDULE-A (PART - B)**Name of the work: Construction of bins for metal parts, scrap insulator yard and waste storage bins.**

SL.NO.	Description	Unit	Qty	Rate	Amount.
1.	Earthwork Excavation for foundation /trenches/leveling and lowering etc and removing the excavated earth up to a lead of 50 mtrs and lift up to 1.50 mtrs in hard soil.	Cum	202.00		
2.	Earthwork filling in foundation and basement with available earth including watering and compaction layers of 15 cm thick up to 50 mtrs lead and lift-1.50 mtrs etc	Cum	202.00		
3.	Providing and laying granite jelly, cement concrete 1:4:8 using 40mm and downsize jelly including mixing, laying and tamping curing and excluding cost of centering & shuttering and plastering, for foundation, flooring, etc. and excluding cost of cement etc, cement will be provided by BHEL for free of cost	Cum	17.10		
4.	Providing and constructing size stone masonry-in C M 1:8 by using granite stone hammer dressed, for foundation, including bond stones at 2.00 mtrs apart in each course., curing , scaffolding etc complete. Excluding the cost of cement, Cement will be provided by BHEL for free of cost.	Cum	90.42		
5.	Providing and laying granite jelly, cement concrete 1:2:4 using 20mm and downsize jelly including mixing, laying and tamping curing and excluding the cost of cantering , shuttering and plastering, for basement, flooring, sills, coping bond slab etc complete. excluding cost of cement , Cement will be provided by BHEL for free of cost.	Cum	16.38		
6.	Providing and constructing size stone masonry in CM 1:6 by using granite stone chiseled dressed, for Super structure, including bond stones at 2.00 m apart in each course., curing etc complete, Excluding the cost of cement, Cement will be provided by BHEL for free of cost.	Cum	129.20		
7.	Providing ruled pointing for size stone masonry / stone slab in CM 1:3 including racking the joints and finishing smooth etc., complete. Excluding the cost of cement. Cement will be provided by BHEL for free of cost.	Sqm	574.20		

8.	Providing plastering in CM 1:4, 20 mm thick for new surface/patches in repair works ,including providing and removing scaffolding rounding of all corners with finishing of lime rendering / Sand finish/water proof addition as required including curing etc complete to burnt brick masonry/Concrete surface etc excluding the cost of cement, cement will be provided by BHEL for free of cost.	Sqm	131.25		
9.	Dismantling size stone masonry in CM and removing the debris and stones up to a distance up to 200m.	Cum	6.75		
10.	Dismantling of steel in built up section using gas cutting machine /welding and stacking the members up to distance of 200 mtrs.	Ton	1.00		
11.	Labour charges for fabricating of truss column, purlins, fencing members/gates/doors etc as shown in drawing which will be issued during execution .with available new steel or by collecting from released structural members by welding/ gas cutting and applying two coats of enamel paint over a coat of red oxide including necessary scaffolding tools and plants up to working height of 9.00 mtrs, detailed fabrication drawings to be submitted by contractor before commencement of work. Steel will be provided by BHEL for free of cost.	Ton	1.00		
12	Labour charges for fabricating and fixing MS/Tor steel reinforcement for Chejjas ,column, beam ,lintel , roof slab, including cutting, bending, tying with binding wire and placing in position etc complete including the cost of binding wire , using new steel or old available scrap steel. Only steel will be provided by BHEL for free of cost. Working height up to 9.00mtrs .	Ton	1.00		
13	Providing and laying reinforced cement concrete 1:2:4 using clean granite jelly of 20mm and downsize for R.C.C. Footings, column, beam, lintel, chajja etc excluding cost of centering & shuttering, and plastering at working height/depth up to 9.00mtrs Excluding the cost of cement. Cement will be provided by BHEL for free of cost.	Cum	1.00		
14	Labour charges for construction size stone masonry in C.M. 1:6 for foundation including cost of dressing, transportation up to 1 K.M. and cement mortar. Cement & stones will be issuedby BHEL for free of cost. Stone chipping for packing in masonry construction to be prepared from available stones etc.	Cum	5.40		
	TOTAL - NETT				
	Taxes if any	%			
	GRAND TOTAL				

Grand total amount in words - Rupees

Signature of the Contractor

Name:

Address:

NOTE : 1. Quantities indicated as above is approximate, the billing will be done at actuals.

2. Taxes if any is to be indicated in the table above; if taxes is not indicated, the rates quoted is assumed to be inclusive of taxes.