

SCHEDULE-A (PART - B)**Name of the work: Providing concrete road for raw material storage bins and closing Crushing Plant Pit**

SL.NO.	Description	Unit	Qty	Rate	Amount.
1.	Earthwork Excavation for foundation /trenches/leveling and lowering etc and removing the excavated earth up to a lead of 50 mtrs and lift up to 1.50 mtrs in hard soil.	Cum	10.00		
2.	Earthwork filling to the Pit with earth brought from outside and Earthwork filling in foundation and basement with available earth including watering and compaction layers of 15 cm thick up to 50 mtrs lead and lift-1.50 mtrs etc	Cum	220.80		
3.	Providing and laying granite jelly, cement concrete 1:4:8 using 40mm and downsize jelly including mixing, laying and tamping curing and excluding cost of centering & shuttering and plastering for foundation, flooring, cills, coping bond slab etc. excluding cost of cement etc, cement will be provided by BHEL for free of cost	Cum	5.00		
4.	Providing and laying, cement concrete 1:2:4 using 20mm and downsize granite jelly including mixing, laying and tamping curing and excluding cost of centering & shuttering and plastering for flooring, sills, coping bond slab etc. excluding cost of cement etc complete.Cement will be provided by BHEL for free of cost.	Cum	1.00		
5.	Providing plastering in CM 1:4, 20 mm thick for new surface/patches in repair works ,including providing and removing scaffolding rounding of all corners with finishing of lime rendering / Sand finish/water proof addition as required including curing etc complete to burnt brick masonry/Concrete surface etc excluding the cost of cement. Cement will be provided by BHEL for free of cost.	Sqm	254.00		
6.	Labour charges for fabricating of truss column, purlins, fencing members/gates/doors etc as shown in drawing which will be issued during execution .with available new steel or by collecting from released structural members by welding/ gas cutting and applying two coats of enamel paint over a coat of red oxide including necessary scaffolding tools and plants up to working height of 9.00 mtrs, detailed fabrication drawings to be submitted by contractor before commencement of work.	Ton	1.00		

7.	Labour charges for fabricating and fixing MS/Tor steel reinforcement for Chejjas ,column, beam ,lintel , roof slab, including cutting, bending, tying with binding wire and placing in position etc complete including the cost of binding wire , using new steel or old available scrap steel. Only steel will be issued by BHEL at free of cost. Working height up to 9.00mtrs .	Ton	18.40		
8.	Providing and laying reinforced cement concrete 1:2:4 using clean granite jelly of 20mm and downsize for R.C.C. Footings, column, beam, lintel, chajja etc excluding cost of centering, shuttering and plastering, and excluding cost of cement, working height up to 9.00mtrs . Cement will be provided by BHEL for free of cost.	Cum	194.74		
9.	Dismantling RCC /Dismantling SSM/ Dismantling brick masonry work of Roof, column, beam & lintel etc and removing the debris up to a distance of 150 m, including cutting the steel rods by using gas cutting plant stacking steel rods at civil store etc. complete.	Cum	12.14		
10.	Dismantling of plastering in cement mortar/lime mortar of walls/ceiling and disposal of debris and shifting the debris up to near waste bins etc., Up to a working height of 7.5 mtrs. Including cost of centering and shuttering etc., complete	Sqm	640.00		
11.	Providing and fixing, centring and shuttering using steel sheets/wooden planks including removing after curing for beams, columns, lintels, RCC roof, chejjas etc. working height/depth up to 9.00mtrs either above or below the floor level.	Sqm	185.20		
	TOTAL - NETT				
	Taxes if any	%			
	GRAND TOTAL				

Grand total amount in words - Rupees

Signature of the Contractor

Name:

Address:

NOTE : 1. Quantities indicated as above is approximate, the billing will be done at actuals.

2. Taxes if any is to be indicated in the table above; if taxes is not indicated, the rates quoted is assumed to be inclusive of taxes.